


Rural Fire District Letter

I hereby certify that the property proposed for Border Region Housing (BRH) rezoning, which is a portion of Tax Lot 501 Map 195 44E 16 and shown on the attached map (include map showing precise location of homesites, lots and/or parcels under review by the Border Region Review Board) within and entitled to fire prevention and suppression services by Vale Rural Fire Protection District.
Rural Fire District Name

The **attached letter** describes fire prevention standards required that must be met prior to final plat approval or home construction, as appropriate.

Signed this 9 day of March, 2026

Signature:  _____

Name: Jess Tolman _____

Title: # Fire/and Ems Chief _____

EXHIBIT # 2 _____

City of Vale Fire and Ambulance

150 Longfellow St N • Vale, OR 97918
Phone: (541) 473-3796 • FAX: (541) 473-9667



eat

02/07/2025

Jana Mitchell

Vale, Or 97918

To whom it may concern,

It has come to the attention of the Fire Department for a new structure at the property across from 2145 Bishop Rd. This area lies within the boundaries of the Vale Rural Fire Protection District. Upon Payment of the annual dues and proper registration with the county the Department will provide fire protection to the property. Membership to the Rural Fire Protection district can be achieved by filling out a Membership form at City Hall. Membership cost are \$150 for Primary address and \$100 for any additional addresses.

An inspection of the property has been completed and has revealed there is current driveway to the site of the existing structure. However, if a new driveway was to be added it needs to meet the International Fire Code any access road must be an all-weather surface that has 20' unobstructed width and 13'6" unobstructed vertical clearance. Any access road must include an improved turnaround on roads greater than 150' in length and not exceed a grade of 10%. If the road is greater than 500' in length minimum access road width is 26'. The driveway must also be capable of supporting live loads of at least 75,000 lbs. The driveway angle of approach\departure cannot be less than the design limitations of the Fire Department apparatus. If you have any questions, please call me at 473-3796

Sincerely,

Jess Tolman

Fire Chief
Vale Fire Department

The City of Vale is an Equal Opportunity Employer/Provider